NOTIFICATION. 464

No. L.D. 2262—Legis. 5-51-105, dated Bangalore, 5th March 1952.

Ordered that Notification Nos. S.R.O. 277 and 278, dated the 12th February, 1952, of the Ministry of Works, Production and Supply amending the Indian Boiler Regulations, 1950, published in the *Gazette of India*, Part II, Section 3, dated the 16th February 1952, be republished in the *Mysore Gazette*, for general information.

By Order of His Highness the Maharaja,

N. R. JAYA RAO,
Legal Remembrancer and
Secretary to Government;
Law Department.

GOVERNMENT OF INDIA.

MINISTRY OF WORKS, PRODUCTION & SUPPLY.

CENTRAL BOILERS BOARD

New Delhi, the 12th February 1952.

S.R.O. 277.—In exercise of the powers conferred by section 28 of the Indian Boilers Act, 1923 (V of 1923) the Central Boilers Board hereby directs that the following amendment shall be made in the Indian Boiler Regulations, 1950, the same having been previously published as required by sub-section (1) of section 31 of the said Act, namely :—

To clause (b) of regulation 166 of the said Regulations, the following shall be added at the end, namely :—

"Lugs may be satisfactorily welded to manhole doors for the attachment of bolts."

[No. M/BL-307 (57).]

S.R.O. 278.—In exercise of the powers conferred by section 28 of the Indian Boilers Act, 1923 (V of 1923), the Central Boilers Board hereby directs that the following amendment shall be made in the Indian Boiler Regulations, 1950, the same having been previously published as required by sub-section (1) of section 31 of the said Act, namely :—

For Regulation 527 of the said Regulations, the following regulation shall be substituted, namely :—

"527. Procedure for Hydraulic test. Every economiser for registration shall be hydraulically tested in the presence of an Inspector to 1½ times the working pressure. Hydraulic tests of economisers at subsequent examinations shall, when required by the Inspector, be made after the inspection. The test pressure to be applied to economisers at subsequent examinations shall be from 1¼ to 1½ times the working pressure of the economisers. During the test, all parts externally and in the flues shall be noted for leakage."

[No. M/BL-304(66).]

N. P. DUBE,
Secretary, Central Boilers Board.